



Geo-Loop Inc. Trailer Package

The leader in geothermal and water well grouting equipment.



This heavily built trailer is especially designed to easily haul the **Geo-Loop 50-500** grouter, grout hose reel, two pallets of grout, and a water tank around the job site. A grout hose reel mounts on the rear of the trailer and holds 500' of 1 1/4" grout line. Other optional hose reels with 1,000' of 1 1/4" grout line capacity available. See the 45 inch, mid set, and deep set hose reels on our website. The trailer is available with two 7,000, 8,000, or 10,000 pound axles and a 2 5/16" ball or pintle hitch.

Getting to the job...

Designed and built by professionals who understand *YOUR* needs.

Trailer Package

Features:

- Specially designed, custom-built trailer-78" x 22'
- Sturdy 14,000 pound rating will meet your needs
- Two standard - 7,000 pound axles with brakes (8,000 and 10,000 pound axles available)
- Heavy duty adjustable hitch (2 5/16" ball or pintle hitch available)
- Generous 500 gallon water tank
- Innovative Geo-Loop grouters
- Small and large hose reels with capacities over 1,000' of 1 1/4" grout line



Maximum theoretical performance shown. Maximum output and pressure can not be reached simultaneously. Performance will vary depending on grout, mix design, and grout line diameter and length. Specifications and products subject to change without prior notice.



For more information contact Jeff Bowen at:
Geo-Loop Inc. • 316 East Ninth Street • Aurelia, Iowa 51005
Phone: 800-580-5965 • 712-434-2125 • Fax: 712-434-2115
Website: www.geo-loop.com • Email: jeff@geo-loop.com